GOVERNMENT OF ANDHRA PRADESH

ABSTRACT

Rural Development – Mahatma Gandhi National Rural Employment Guarantee Scheme (MGNREGS) – Revision of Rural Standard Schedule of Rates, 2018-2019 (RSSR 2018-2019) – Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.MS.No. 29 **Dated: 16-04-2018**

Read the following:

1) G.O.Ms.No.36, PR&RD (RD.II) Dept,, Dated:28.06.2017.
2) From the GoI, MoRD Letter F.No.J-11011/1/2009-RE-III Dt.31.03.2018.
3) From the Director, Panchayat Raj & Rural Development e-file No.3646/EGS/SPM(T)/2016-1 Dt.07.04.2018.

<<0>>

ORDER:

In the G.O first read above, Government have issued orders modifying Rural Standard Schedule of Rates as per the wage rate enhanced by the Government of India under MGNREGA from Rs.194/- to Rs.197/- per day for the year 2017-2018.

2. In the reference third read above, the Director, Panchayat Raj & Rural Development, AP, Vijayawada has requested the Government to enhance of task rates of Rural Standard Schedule of Rates for the Financial Year 2018-2019 based on the wage rate enhanced by the Government of India in the reference second read above from Rs.197/- to Rs.205/- per day for the financial year 2018-2019.

3. Government after careful examination of the proposal, hereby enhance task rates of Rural Standard Schedule of Rates for the Financial Year 2018-2019 as detailed in the Annexure to this order based on the wage rate enhanced by the Government of India from Rs.197/- to Rs.205/-.

4. The Director, Panchayat Raj and Rural Development shall take necessary further action accordingly.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

Dr. K.S. JAWAHAR REDDY
PRINCIPAL SECRETARY TO GOVERNMENT (PR&RD)

To:

The Director, Panchayat Raj and Rural Development, AP., Vijayawada
All the District Collectors and District Programme Coordinators, NREGS in the State.
All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS in the State.
All the Project Directors, DRDAs and Additional District Programme Coordinators, NREGS in the State.
All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS in the State.
The Project Officer, ITDA and Additional District Programme Coordinators of Parvathipuram (Vizianagarm), Srisailam (Kurnool), Paderu (Visakhaptnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari)

Copy to:

The PS to Prl. Secretary, PR & RD
The PS to Prl. Secretary, Irrigation (I&CAD).
The PS to Prl. Secretary, Tribal Welfare Dept.
The PS to Prl Secretary, R&B.
The PS to Prl. Secretary, EFS & T Dept.
The PS to Prl. Chief Conservator of Forests.
The PS to Commissioner Disaster Management.
The PS to Commissioner, Tribal Welfare.
The PS to Engineer-in-Chief, Panchayat Raj Dept.
The PS to Engineer-in-Chief, Irrigation Dept.
The PS to Chief Engineer, Tribal Welfare Dept.
The Secretary, APREG Council.
The PS to Hon'ble Minister (PR,RD, ITE&C).
The PS to Spl Secretary(PR&RD).
SF/SC.

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE to GO Ms.No.29,PR&RD (RD-II) Department, Dated:16.04.2018

Sl. No.	Category No.	Item of Work	Rates approved in RSSR (GO.Ms.No. 36 PR&RD (RD-II)Dept., dated 28.06.2017 (in Rs.)	Rates now approved to ensure maximum Wage of Rs.205/- (in Rs.)	Remarks
1		**Unskilled Labour**	197.0/ per day	205.0/ per day	-
2	**Bush clearance**				
	a	Light shrub	4.88/sqm	5.07/sqm	-
	b	Medium and Dense Shrub /Besharam/ Rubber plants	6.17/sqm	6.42/sqm	-
	c	Thin stemmed Juliflora (stem with periphery upto 150 cms)/ thick shrub	11.38/sqm	11.84/sqm	Thick shrub is relevant in tribal areas only
	d	Thick stemmed Juliflora (stem with periphery more than 150 cms	18.38/sqm	19.12/sqm	-
3	**Removal of stumps**				
	a	Removal of stumps of girth 30cms to 99cms(small stumps)	142.27 per each	148.04 per each	-
	b	Removal of stumps of girth 100cms to 199cms(medium stumps)	160.03 per each	166.52 per each	-
	c	Removal of stumps of girth 200cms to 299 cms(large stumps)	208.02 per each	216.46 per each	-
	d	Removal of stumps of girth 300cms to 399 cms(large stumps)	272.05 per each	283.09 per each	-
	e	Removal of stumps of girth 400cms to 499 cms(large stumps)	352.08 per each	366.37 per each	-
	f	Removal of stumps of girth 500cms to 599 cms(large stumps)	432.06 per each	449.6 per each	-
4		Removal of water hycinth up to 30cms thick	6.07 /Sqm	6.31 /Sqm	-
5		Removal of water hycinth of more than 30cms thick	8.30/Sqm	8.63/Sqm	-

6	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in loamy and clayey soils like black cotton soils, red earth and chowdu soils (Ordinary soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	116/ Cum	120.71/ Cum	-
	b	Category II (Trench Cutting works)	197/ Cum	205/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	226.96/ Cum	236.17/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	242.84/ Cum	252.7/ Cum	-
	e	Category IV (Pitting works)	167.40/ Cum	174.19/ Cum	-
	f	Category V (Desilting works)	116.00/ Cum	120.71/ Cum	-
7	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in Hard soils like gravel, moram., (Hard soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	197/ Cum	205/ Cum	-
	b	Category II (Trench Cutting works)	221.57/ Cum	230.56/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	255.90/ Cum	266.29/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	289/ Cum	300.73/ Cum	-
	e	Category IV (Pitting works)	197 / Cum	205/ Cum	-
8	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soils with mixture of gravel, pebble and soft disintegrated rock like shales ordinary gravel, stoney earth and earth mixed with fair sized boulders (Stoney earth)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	207.93/ Cum	216.37/ Cum	-
	b	Category II (Trench Cutting works)	216.68/ Cum	225.47/ Cum	-
	c	Category III (ponds) up to 1.00 m depth	300.08/ Cum	312.26/ Cum	-
	d	Category III (ponds) beyond 1.00 m depth	312.70/ Cum	325.39/ Cum	-
	e	Category IV (Pitting works)	207.93/ Cum	216.37/ Cum	-
9	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soft disintegrated rock soils (removable by pick axes and crow bars) (SDR Soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	221.57/ Cum	230.56/ Cum	-
	b	Category II (Trench Cutting works)	262.64/ Cum	273.3/ Cum	-

10	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in silt in canals, channels and drains**				
	a	Feeder/Field Channel and Irrigation drains upto 1.0 mt depth	86.13/ Cum	89.62/ Cum	-
	b	Renovation of spring channels			
11	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in sandy soils or loose soils/wet sand not under water**				
	a	Land levelling for land development and Flood control Project	65.08/ Cum	67.72/ Cum	-
12	a	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	29.50/ Rmt	30.69/ Rmt	-
13	**Carrying of earth / gravel by head loads – Leads & Lifts**				
	a	For every additional Lead of 10 mts over and above initial lead of 10mt	24.58/ Cum	25.57/ Cum	-
	b	For every additional lift of 1mt over and above initial lift of 2mts	24.58/ Cum	25.57/ Cum	-
14	**Conveyance of silt , carted earth, stable casing soil and gravel excluding loading and unloading**				
	a	up to 1 km	58.50/-cum	**Conveyance charges shall be as per Common SSR**	
	b	2 km	68.25/-cum		
	c	3 km	78/-cum		
	d	4km	87.75/-cum		
	e	5km	104/-cum		
	f	6km	107/-cum		
	g	7 km	120/-cum		
	h	8 km	132/-cum		
	i	9 km	138/-cum		
	j	10 km	143/-cum		
15		Labour charges for Spreading of silt unloaded by tractor in the field	23.89/ Cum	24.86/ Cum	-
16		Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	37.22/ Cum	38.73/ Cum	-
17	**Pebble bunding**				
	a	Small stone (size more than 40mm) bunding- Labour charges for collecting and putting as bund only.	258.51/ Cum	269/ Cum	-
18	**Stone revetment (Un skilled)**				
	a	Labour charges for revetment for all type of works	430.86/ Cum	448.35/ Cum	-
19	**Rough Stone Dry Packing & Stone pitching (Unskilled)**				
	a	Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	246.20/ Cum	256.19/ Cum	-
	b	Stone Terracing – Labour charges for packing only.	246.20/ Cum	256.19/ Cum	-

20	**Plantation works**				
	Category : I				
	a	Survey and demarcation	31.96/- per100 nos	33.25/- per100 nos	-
	b	Alignment and fixing of planting point with 0.45 meters length sticks	92.25/- per100 nos	95.99/- per100 nos	-
	c	0.45 meter sticks preparation and transportation at site.	49.20/- per100 nos	51.19/- per100 nos	-
	d	i) Internal transportation of bag plants to planting points. (5"x9")	49.20/- per100 nos	51.19/- per100 nos	-
		ii) Internal transportation of Avenue Plantation. Tall plants	191.04/- per100 nos	198.79/- per100 nos	-
	e	**Refilling of Pits and planting (mxmxm), staking stick**			
		i) 0.30 X 0.30 X 0.30 Size pit	1.15/- each	1.19/- each	-
		ii) 0.45 X 0.45 X 0.45 Size pit	3.60/- each	3.74/- each	-
		iii) 0.60 X 0.60 X 0.60 Size pit	7.34/- each	7.63/- each	-
		iv) 0.90 X 0.90 X 0.90 Size pit	11.00/- each	11.44/- each	-
		v) 1.00 X 1.00 X 1.00 Size pit	12.27/- each	12.76/- each	-
	Soil working and weeding				
	Category : I (1 M dia and 0.1 m Depth)				
	a	Avenue Plantation	12.27/- each	12.76/- each	-
	b	Horticulture	12.27/- each	12.76/- each	-
	Category : II (0.5 M dia and 0.1 m Depth)				
	a	Fore shore plantation	3.62/- each	3.76/- each	-
	b	B.H.Afforestation	3.62/- each	3.76/- each	-
	c	Bio Diesel Plantation & Block plantation	3.62/- each	3.76/- each	-
21	**Causality Replacement for**				
	a	Reopening of Pits for avenue, Horticulture & Blok Plantations.	12.47/- each	12.97/- each	-
	b	Fore share plantation, Barren Hill Afforestation, Bio-Diesel	6.07/- each	6.31/- each	-
22		Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	197/- day	205/- day	-

23	**Bio Fencing / Brush Wood Fencing for barren hill afforestation.**				
	a	Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	24.57/- Rmt	25.56/- Rmt	-
	b	Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	93.14/- each	96.92/- each	-
	c	Horticulture, for lands of SC-ST & Assignee lands only	2462.20/- acre	2562.18/- acre	-
	d	Horticulture fencing 1st year & 2nd year maintenance SC-ST& Assignee lands only.	615.52/- acre	640.51/- acre	-
24	**Deep Ploughing in**				
	a	Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1627.32/- acre	1693.4/- acre	-
	b	fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	1302.29/- acre	1355.17/- acre	-
	c	Cattle cultivator (Double ploughing) in ordinary soils.	977.92/- acre	1017.63/- acre	-
25		Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	3.12/- plant	3.24/- plant	-
26		Watering plants from hand pump/bore well/open well up to distance of 30 mt	4.39/- plant	4.56/- plant	-
27		Watering block plantation from the nearby sources ie., bore well open well or kunta beyond 30 mts distance.	5.46/- plant	5.68/- plant	-
28		Hire charges of tractor mounted water tanker for filling sump	489.18/- per one trip of 5000 ltrs capacity	509.04/- per one trip of 5000 ltrs capacity	-
29		Sharpening of crowbar	15/- per day	15/- per day	No change
30		Basket Replenishment charges	5/- per day	5/- per day	No change

Dr. K.S. JAWAHAR REDDY
PRINCIPAL SECRETARY TO GOVERNMENT (PR&RD)